

2060 WABASH ST.
DETROIT, MI 48216
www.bioLINIA.com

1588 ELM, DETROIT, MI 48216

BALLET REAL ESTATE
1701 Trumbull Ave. #5
Detroit, MI 48216
Phone: (415) 279 0953

DESIGNER

Becky Nix, LEED(AP) - PRINCIPAL IN CHARGE

LM ENGINEERING
25315 Dequindre Rd.
Madison Heights, MI 48071
Phone: (248) 672 1895
Email: Lawrence@LM-Engineering.net


GENERAL CONTRACTOR

Shane Overbey - Builder License #2101207828

1ST FLOOR PLAN & REFLECTED CEILING PLAN

Project number	2019_1588
Date	11/30/2020
Drawn by	BN
Checked by	BN
Scale	1/4" = 1'-0"

12/3/2020 2:28:40 PM




- THIS DRAWING IS DIAGRAMMATIC AND SHOULD BE USED TO DETERMINE THE DESIGN INTENT. THE CONTRACTOR IS RESPONSIBLE FOR THE COMPLETE SET OF WORK AS INDICATED AND SHALL FIELD VERIFY THE EXISTING CONDITIONS. DRAWINGS ARE NOT TO BE USED TO DETERMINE THE EXISTENCE OF ANY DISCREPANCIES IN THE DOCUMENTS BEFORE PROCEEDING. FAILURE TO DO SO WILL RESULT IN THE CONTRACTOR TAKING FULL RESPONSIBILITY AND LIABILITY FOR SAID DISCREPANCIES.
- ALL DIMENSIONS ARE SHOWN FROM FINISHED FACE TO FINISHED FACE UNLESS OTHERWISE NOTED.
- WALL THICKNESS ARE NOMINAL NOT ACTUAL DIMENSIONS. SEE WALL TYPES FOR ACTUAL DIMS.
- PROVIDE POSITIVE SLOPE TO ALL FLOOR DRAINS WHILE KEEPING FLOOR LEVEL AT WALL BASE CONDITION.

- REINFORCE WALL AND PROVIDE BRACING AS REQUIRED TO SUPPORT WALL CABINETS, COUNTERTOPS, COATHOOKS AND ANY OTHER WALL-MOUNTED MILLWORK/EQUIPMENT, AND ACCESSORIES.
- THE CONTRACTOR SHALL PROVIDE AND INSTALL WALL REINFORCING FOR INSTALLATION OF ACCESSORIES, CASEWORK, AND OTHER WALL MOUNTED ITEMS.
- PROVIDE CONTROL JOINTS IN GYPSUM BOARD PARTITIONS AT 24" o.c. MAXIMUM AND AS INDICATED IN THE CONTRACT DOCUMENTS.
- COORDINATE WITH OWNERS EQUIPMENT SUPPLIER FOR INSTALLATION REQUIREMENTS / LOCATIONS OF FLOOR, WALL, CEILING MOUNTED ITEMS; IE: CAMERAS, SENSORS, SECURITY WIRING, & COMMUNICATION
- CONTRACTOR SHALL CONDUCT A RUGH ELECTRICAL INSPECTION WITH OWNER, PRIOR TO ENCLOSING THE WALLS. FOR THE PURPOSE OF CONFIRMING ALL J-BOX LOCATIONS FOR POWER, DATA, VOICE, SWITCHES, THERMOSTATS, ETC.

CEILING NOTES

- REFER TO FINISH SCHEDULES/SPECIFICATIONS CEILING FINISH INFORMATION
- COORDINATE ALL WORK WITH MECH. & ELEC. PLANS
- EXPOSED CONDUIT NOT TO BE USED UNLESS EXPRESSLY APPROVED BY ARCHITECT.

CEILING KEY



5/8" TYPE "X" GYPSUM BOARD CEILING, FRAME AS
REQ'D