

FAN SCHEDULE												
EQUIPMENT TAG	AIRFLOW (CFM)	ESP	FRPM	DRIVE	ELECTRICAL					MODEL NUMBER	MANUFACTURER	REMARKS
					POWER (W)	RPM	VOLT	PHASE	MCA			
EF-1	80	0.25	935	DIRECT	6	--	115	1	0.05	SP-80-VG	GREENHECK	FAN SHALL OPERATE CONTINUOUSLY
EF-2	80	0.1	--	DIRECT	23.3	--	120	1	0.2	QTXEN080	NUTONE	FAN SHALL OPERATE WITH LIGHT SWITCH
EF-3	80	0.1	--	DIRECT	23.3	--	120	1	0.2	QTXEN080	NUTONE	FAN SHALL OPERATE WITH LIGHT SWITCH
EF-4	80	0.1	--	DIRECT	23.3	--	120	1	0.2	QTXEN080	NUTONE	FAN SHALL OPERATE WITH LIGHT SWITCH

NOTE:
1. PROVIDE 1/2" UNDERCUT IN ALL TOILET ROOM DOORS.

ROOFTOP UNIT SCHEDULE																							
EQUIP TAG	FAN					COOLING						HEATING								DIMENSIONS HxWxL (IN)	WEIGHT (LB)	YORK (BASE BID)	REMARKS
	AIRFLOW (CFM)		CONTROL	DRIVE TYPE	ESP	MIXED AIR		UNIT LAT °F	TOTAL (MBH)	SENS (MBH)	SEER	INPUT (KW)	MAT °F	LAT °F	SUPPLY FAN MOTOR (HP)	VOLT	PHASE	MCA					
	SUPPLY AIR	OUTSIDE AIR				DB °F	WB °F																
RTU-1	800	160	CONSTANT VOLUME	BELT	0.6	80.0	67.0	60.5	24.4	16.9	14.0	10	56.0	84.4	0.5	208	1	47.1	47x36x52	400	PCE4A2422		

NOTE: 1. SCHEDULED CAPACITIES ARE REQUIRED VALUES. ALTERNATE MANUFACTURERS: LENNOX AND CARRIER.
2. UNIT SHALL COMPLY WITH NFPA 70 AND ASHRAE 90.1.
3. PROVIDE ECONOMIZER, BAROMETRIC RELIEF, FACTORY ROOF CURB, 2" PLEATED AIR FILTERS, FACTORY INSTALLED PACKAGE WITH NEMA 34 NON-FUSED UNIT DISCONNECT SWITCH, NON-POWERED DUPLEX RECEPTACLE, ELECTRONIC IGNITION, STARTER, PHASE MONITOR, PHOTO-ELECTRIC SMOKE DETECTOR IN RETURN DUCT (COORDINATE WITH PROVIDER SIMPLEX).
4. ELECTRICAL DATA, DIMENSIONS AND WEIGHTS ARE BASED ON THE "BASE BID" UNIT. IF ALTERNATE MANUFACTURERS ARE USED, COORDINATE CHANGES WITH ELECTRICAL, STRUCTURAL AND ARCHITECTURAL TRADES. ANY ADDITIONAL COSTS DUE TO CHANGES RESULTING FROM USE OF ALTERNATE MANUFACTURERS SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR. REFER TO MECH SPECIFICATIONS.

ELECTRIC UNIT HEATER SCHEDULE								
TAG	TYPE	CFM	OUTPUT (KW)	ELECTRICAL			MODEL NUMBER	REMARKS
				VOLT	PHASE	FLA		
UH-1	VERTICAL	1340	15	208	3	0.33	VE150	

NOTE: 1. MODEL NUMBERS ARE MODINE UNLESS OTHERWISE NOTED.
2. PROVIDE HONEYWELL TS822 THERMOSTAT WITH GUARD.
3. FURNISHED AND INSTALLED BY MECHANICAL CONTRACTOR, WIRED BY ELECTRICAL CONTRACTOR.
4. UNITS SHALL COMPLY WITH NFPA 70 AND ASHRAE 90.1.
5. PROVIDE UNIT MOUNTED DISCONNECT SWITCH.

SPLIT SYSTEM SCHEDULE																							
INDOOR UNIT									ELECTRICAL				OUTDOOR UNIT						ELECTRICAL				REMARKS
EQUIPMENT TAG	AIRFLOW (CFM)	COOLING TOTAL (MBH)	COOLING SENSIBLE (MBH)	HEATING INPUT (MBH)	HEATING OUTPUT (MBH)	DIMENSION HxWxL (IN)	WEIGHT (LBS)	YORK MODEL NUMBER	VOLT	PHASE	MCA	MOP	EQUIPMENT TAG	DIMENSION HxWxL (IN)	WEIGHT (LBS)	SEER	YORK MODEL NUMBER	VOLT	PHASE	MCA	MOP		
AC-1	800	24.0	16.8	80	64	36x20x32	110	TM8Y080B12MP11	115	1	9.3	15	ACC-1	40.2x34.5x38.2	195	16	YFK24B21S	208	1	15.3	25		
AC-2	600	18.2	13.9	80	64	36x20x32	110	TM8Y080B12MP11	115	1	9.3	15	ACC-2	36.2x24x24	120	16.25	YFE18B21S	208	1	11.8	20		

NOTES:
1. ALTERNATE MANUFACTURERS: LENNOX & CARRIER.



RAM MECHANICAL CONSULTING
8521 CHURCH ROAD
GROSSE ILE, MI 48138
(586) 666-1062

SEAL



THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION PURPOSES UNTIL THE SEAL AND SIGNATURE OF THE RESPONSIBLE REGISTRANT APPEARS ON THE DRAWING, AND PROPER PERMIT FORMS AND RELATED FEES ARE TRANSMITTED BY THE OWNER, OWNER'S AGENT OR CONTRACTOR TO THE AUTHORITY HAVING JURISDICTION.

CONSULTANT

CLIENT

Brian Mulloy

PROJECT

1588 Elm St.
Detroit, MI 48216

REVISIONS

06-26-2020 PERMIT

TITLE

MECHANICAL
SCHEDULES

SHEET

M3